

INTERNAL



Duke Energy Florida – Solar Generation

February 2026


Duke Energy Florida

Vanessa.Goff@duke-energy.com



Project Development Phases


Developers originate a pipeline of renewable assets through greenfield development and strategic acquisitions



Identify Gate

- Transmission Availability
- Site Buildability
 - Wetland
 - Floodplains
 - Slope
 - Sink Holes
 - Site Access

- Site Due Diligence
 - ESA Phase 1
 - Habitat Assessments
 - Gopher Tortoises
 - Scrub Jay
 - American Kestrel
 - Cultural Assessments
 - Geotechnical Assessment
 - Perk Tests
 - Soil corrosivity
 - Soil Make up - Borings
 - Pull Tests
 - Title Risk



Solar Growth in Florida for Duke Energy


- Between 2025 and 2027, Duke Energy is adding 12 new solar sites to the electric grid, increasing capacity by 900 megawatts.
- Between 2028 and 2030, Duke Energy is looking to add 15 to 18 new solar sites to the electric grid along with battery storage
- Expanding solar energy reduces the need for fuels like natural gas to generate electricity, resulting in direct savings for customers since the price Duke Energy Florida pays for fuel is a direct pass-through cost reflected on their bills. In this case, every four sites will save the company's 2 million customers an estimated \$1 billion over the sites' operational lifetimes.
- Duke Energy is passing on approximately \$65 million in IRA production tax credits in 2025, and that amount will grow each year as more solar is placed in service, reducing residential rates by at least \$2.50 per 1,000 kWh on their monthly bill.



Changes in State and Federal Legislation

- Production Tax Credits (PTCs) and Investment Tax Credits (ITC)
 - ITC - 30%+ credit on installation costs, domestic content adds 10%
 - PTC - a 10-year, per-kWh credit
- One Big Beautiful Bill
 - Sunset to PTCs and ITCs for renewables by December 2030
 - Wind and solar projects must begin construction by **July 4, 2026**, or be placed in service by **December 31, 2027**, to qualify for full PTC/ITC
 - To demonstrate Start of Construction, must pass Physical Work Test, which requires physical work of a significant nature (on-site or off-site) to be started and remain continuous.
 - Must meet prevailing wages and have an apprenticeship programs
 - Foreign Entity of Concern (FEOC) restrictions on projects starting construction after July 4, 2026, or placed in service after Jan. 1, 2028
 - No more than 40% of the costs to build the site can be from a prohibited foreign entity (increasing by 5% each year)
 - Main impacts are Solar Modules, Inverters, wiring
 - Florida Senate Bill 1173 & Florida House Bill 905 appear similar to the federal guidance on FEOC.

Construction Schedule



INTERNAL

Installation of Fencing and Vegetative Buffers



Traditional fencing choices have frequently been chain link with security wire, due to security and electrical safety concerns.

We will work with communities to offer the best solution.



Utilize setbacks and existing vegetation where possible or plant new vegetation that will grow over time.

INTERNAL

Construction Process – Site Mobilization/Clearing



INTERNAL

Construction Process – Trenching/Cable Installation



INTERNAL

Construction Process – Post & Racking Installation



INTERNAL

Module Installation



Installation of
DEF's 1,000,000th
Module

INTERNAL

Installation of Inverters and Combiner Boxes



INTERNAL

Construction Process - Interconnection



INTERNAL

Project Operation – Placed in Service



INTERNAL

Post Operation – Project Decommissioning

Modules

- Shipped to an existing site or salvaged
- Over 90% of a solar panel is recyclable
- Remaining disposed off in accordance with local requirements

Inverters/ Cables/Racking

- Cables and electrical equipment (inverters) deemed no longer necessary are removed and recycled by approved recycling facilities
- Racking is comprised of steel, and are recycled by an approved metals recycler

Land Use

- Following removal of equipment, site is returned to its initial condition
- Site is tilled to restore sub-grade materials
- Biodiversity is maintained as part of vegetation management plans

**Decommissioning process ranges between 2-6 months*

